

## ADDENDUM 1

**Project:** LC-Customer Service Center  
Roofing System Replacement  
WJE No. 2019.3919

Lane County Public Works  
General Services  
Eugene, Oregon 97408  
Phone: 541-682-6920  
E-mail: Betty.Mishou@lanecountyor.gov

**Date:** February 16, 2021

**To:** Interested Bidders

**Prepared by:** Architect/Engineer  
WJE Engineers & Architects, P.C. (WJE)  
960 South Harney Street  
Seattle, Washington 98108  
Contact: Rocco Romero  
Phone: 206-890-8407  
E-mail: rromero@wje.com

This Addendum modifies the Project Manual, Specifications, and Drawings as follows:

1. On Sheet A200 of the Drawings, INSULATION LAYOUT LEGEND, Item (E), should be changed to:  
  
2 1/2 INCH FLAT STOCK INSULATION PLUS 1/8 INCH PER FOOT TAPERED INSULATION TO MATCH SLOPE OF ROOF AREA B.
2. In Specification Section 07 42 13 PREFORMED METAL PANELS, Item 2.1.G.2, Taylor Metal Products is included as an approved material manufacturer.
3. In Specification Section 07 54 23 THERMOPLASTIC POLYOLEFIN (TPO) ROOFING, Item 2.1.A.1, GAF Everguard is included as an approved material manufacturer.
4. In Specification Section 06 10 00 ROUGH CARPENTRY, Item 2.3.F, the thickness of the plywood panels should be changed from 1 inch to 1/2 inch.